No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		694
33	Teakwood wrought and put up including wood oiling 2 coats ...	C. ft.		259	
34	Teakwood planks 1" thick	S. ft.		60	
35	Roofing with 4" to 4½" thick slabs and 4½" concrete including grouting the joints with cement concrete plastering with chunam above and cement pointing below.	Sq.		388·03	
36	Roofing with 1st class Mangalore tiles on teak reepers ...	"		24·49	
37	Roofing with pukka terrace with brick on edge flat tiles, plastering, etc., complete.	"		4·13	
38	Ridge tile set in mortar	R. ft.		160	
39	Constructing dormer windows glazed with wood work, roofing, etc., complete.	Each		4	
40	Plain slabbed cornice with concrete slope above including cement plastering. Projection 1½ foot from wall.	R. ft.		899	
41	Plain slabbed cornice with concrete slope above including cement plastering. Projection 2½ feet from bressummer.	"		1,553	
42	Brick masonry cornice 12" thick including cement plastering ...	"		917	
43	Do dental cornice 12" thick with cement plastering	"		147	
44	Slabbed parapet wall with bottom slab resting on stone seats and top slab complete fixed in cement as per design.	"		2,308	
45	Constructing brick masonry or concrete pillasters, 9"×9"×2½' with caps including cement plastering complete.	Each		392	
46	Brick masonry parapet wall 4½" thick 1'—9" high with pillasters and cement plastering, complete.	R. ft.		1,002	
47	Filling in earth and forming platform with good consolidation ...	C. yds.		484	
48	Reinforced concrete slabs	S. ft.		1,296	
49	Flooring with 2" cement concrete over 2½" ordinary concrete ...	Sq.		320·21	
50	Ornamental cut stone brackets	Each		30	
51	Cutting the corners of slabs (in fruit stalls)	Per stall		20	
52	Cutting grooves in pillars	R. ft.		144	
53	Providing cross slab (roughly dressed) over drain	S. ft.		2,517	
54	Providing iron hooks	Each		695	
55	Preparing and fixing expanded metalled revolving meat safes ...	"		48	
56	Do poultry cage with asbestos sheets at top and for horizontal partitions and expanded metal for front and sides with painting as per design.	R. ft.		78	
57	Ornamental cast iron railings with finials, etc., complete ...	L. S.			
58	Providing galvanised zinc water down pipes 3" diameter including bends, etc, complete.	R. ft.		67	
59	Finishing the wall above breassummer with mortar panels, cornice, etc., complete.	L.S.			
60	Constructing compound wall 6' high from ground	R. ft.		1,250	
61	Do 5½' do	"		163	
62	Do 4' do	"		970	
63	Providing wrought iron gates	Each		4	
64	Constructing U shaped concrete drain with cement plastering, side and top slabs, complete.	R. ft.		4,250	
65	Forming road 24' wide with 9" thick gravel	R. yd.		180	
66	Do 15' 9" do	"		260	
67	Do 9' 6" thick gravel	"		1,000	
68	Providing glass tiles to main entrance	Each		40	
	Note—For stone in mortar, the stones obtained from dismantling the Fort wall may be utilized.				

K. P. PUTTANNA CHETTY,
Chairman.

CHITALDRUG DISTRICT.

Notice dated January 1919.

Notice is hereby given that an application has been received from one Bhima Rao, Shanbhog for the grant of the Bechirak Arasur village site, Chitaldrug Taluk for cultivation on ordinary assessment in force in the locality. Persons desirous of bringing in fresh settlers to the village or of otherwise repopulating the village may apply to the undersigned within three months of the date of this notice.

C. B. LAKSHMANA RAO,
For *Deputy Commissioner.*

THE BANGALORE WOOLLEN, COTTON AND SILK MILLS Co., LTD.

Notice dated 12th February 1919.

The transfer books of the Company will be closed from the 17th to 24th February 1919, both days inclusive.

By order of the Directors,
Binny & Co., Ltd.,
J. W. CHAMBERS,
Manager,
Agents, Secretaries and Treasurers,
The Bangalore Woollen, Cotton and Silk Mills Co., Ltd.